BRUHAT BANGALORE MAHANAGARA PALIKE , DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

SCHDULE-B

Name of Work : Improvements to drains at Nisarga Layout 1st, 2nd & 3rd cross road in Ward No 14

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in **Ordinary soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications	Cum	**90.36**	75.60	Rupees Seventy Five & Sixty Paise Only
2	**Removing B.S.Slab** of drain and stacking etc., complete	Sqm	**271.08**	58.32	Rupees Fifty Eight & Thirty two Paise only
3	Providing and laying in position **plain cement** concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	**Cum**	**67.77**	4847.04	Rupees Four thousand Eight hundred Forty Seven & Four Paise only
4	Providing and laying in position plain cement concrete of mix **M1:2:4 with** cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	**Cum**	**28.87**	5228.98	Rupees Five Thousand two hundred twenty eight & Ninty eight Paise Only
5	**Refixing stone slabs** of drains and pointing in CM 1:3 etc complete	Sqm	**271.08**	75.60	Rueeps seventy five & sixty paise only
6	**Providing Granite slabs** selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc.,	Sqm	**229.32**	639.36	Rupees Six hundred thirty nine & Thirty six Paise only
7	Providing and constructing precast **concrete solid blocks** with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size **40x20x20** cms conforming to I.S. 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	**401.60**	993.60	Rupees Nine hundred ninty three & Sixty Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

8	Supplying and fixing **precast** rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Cum	451.80	1600.00	Rupees One thousand Six hundred Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)	Cum	**90.36**	78.24	Rupees Seventy eight & Twenty four Paise Only.

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer
Dasarahalli Division